

| SI No | Item Name                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      | Unit | Estimate Quantity | Negotiated Rates quoted by Sri GANGULU REDDY A |                                     |
|-------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|-------------------|------------------------------------------------|-------------------------------------|
|       |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |      |                   | Rate in figures                                | Rate in words                       |
| 101   | SUMP ( 25,000 LTRS CAPACITY)<br>Earth work excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5m in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m after breaking of clods complete as per specification with all lead and lifts and directions of the Engineer-In-Charge of the work                                                                                                                                                                                                                                                                                                                                                                                         | Cum  | 38.83             | 317.00                                         | Rs. Three Hundred Seventeen only    |
| 102   | Providing and laying in position Plain Cement Concrete of mix 1:3:6 with OPC cement @ 220kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.892 cum and fine aggregates @ 0.465cum machine mixed, concrete laid in layers not exceeding 15 cms thick, well compacted, in foundation including cost of all materials, labour, HOM of machinery, curing complete as per specifications. with all lead and lifts and directions of the Engineer-In-Charge of the work                                                                                                                                                                                                                                                                                                                                                                                                                        | Cum  | 2.40              | 5400.00                                        | Rs. Five Thousand Four Hundred only |
| 103   | Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness including cost of all materials, labour complete as per specifications and direction of the Engineer in charge. with all lead and lifts and directions of the Engineer-In-Charge of the work                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              | Sqm  | 55.44             | 320.00                                         | Rs. Three Hundred Twenty only       |
| 104   | Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for flat surface such as roofs landings balconies and like thickness upto 200 mm including cost of all materials labour complete as per specifications upto 3.50 m from Ground level with all lead and lifts and directions of the Engineer-In-Charge of the work                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             | Sqm  | 14.80             | 20.00                                          | Rs. Twenty only                     |
| 105   | Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.878cum and fine aggregates @ 0.459cum, with superplasticiser @ 3lts confirming to IS9103-1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintels, retaining walls, return walls, walls ( any thickness ) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc., including cost of all materials, labour, HOM of machinery, curing, complete as per specifications with all lead and lifts and directions of the Engineer-In-Charge of the work | Cum  | 9.70              | 6300.00                                        | Rs. Six Thousand Three Hundred only |

Signature of the Contractor  


| SI No | Item Name                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              | Unit | Estimate Quantity | Negotiated Rates quoted by Sri GANGULU REDDY A |                                      |
|-------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|-------------------|------------------------------------------------|--------------------------------------|
|       |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |      |                   | Rate in figures                                | Rate in words                        |
| 87    | Providing and applying painting in two coats with plastic Emulsion paint of approved brand on wall surface to give an even approved shade after thoroughly brushing the surface, free from mortar drops and other foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour, complete as per specifications and as per the directions of the Engineer in charge. (with Primer) with all lead and lifts and directions of the Engineer-In-Charge of the work                                                                                                                                                                                 | Sqm  | 627.77            | 95.00                                          | Rupees Ninety Five only              |
| 88    | Providing and applying painting in two coats with plastic Emulsion paint of approved brand on ceiling surface to give an even approved shade after thoroughly brushing the surface, free from mortar drops and other foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour, complete as per specifications and as per the directions of the Engineer in charge with primer with all lead and lifts and directions of the Engineer-In-Charge of the work                                                                                                                                                                                 | Sqm  | 327.74            | 100.00                                         | Rupees one Hundred only              |
| 89    | Providing ACE paint to external walls of approved colour and shade over prime's coat after brooming & cleaning the surface and applying two coats of ACE paint with cost of all material, labour, lead lift with loading unloading etc. complete as per direction of Engineer in charge of work. with all lead and lifts and directions of the Engineer-In-Charge of the work                                                                                                                                                                                                                                                                                                          | Sqm  | 385.15            | 202.00                                         | Rupees Two Hundred Two only          |
| 90    | Providing and fixing Stainless steel 304 grade for staircase railings balconies ramps with hand rail 50mm dia 16 gauge hollow pipe welded to vertical hollow 50mm dia pipe of 16 gauge, stainless steel vertical pipe spaced at 1.20m regular intervals, and 5 Nos of 25mm dia. Stainless steel hollow horizontal pipe are welded to vertical 50mm dia hollow pipe. The entire assembly is fixed to staircase concrete by using expansion bolts by drilling concrete etc., complete including cost of materials, labour, HOM of machineries and electrical charges, etc., complete as per specifications. with all lead and lifts and directions of the Engineer-In-Charge of the work | Sqm  | 20.00             | 6000.00                                        | Rupees Six Thousand Six Hundred only |
| 91    | Applying priming coat over new wood surface and/ or wood based surface after preparing the surface after thorough cleaning oil, grease, dirt and foreign matter, sand papering and knotting liquid wood filler, for varnish including cost of materials, labour, complete as per specifications. with all lead and lifts and directions of the Engineer-In-Charge of the work                                                                                                                                                                                                                                                                                                          | Sqm  | 137.50            | 46.00                                          | Rupees Forty Six only                |

*Sri Gangulu Reddy*

*Rs 1 - 1/2*

| SI No | Item Name                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             | Unit | Estimate Quantity | Negotiated Rates quoted by Sri GANGULU REDDY A |                                        |
|-------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|-------------------|------------------------------------------------|----------------------------------------|
|       |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |      |                   | Rate in figures                                | Rate in words                          |
| 80    | Providing and fixing M.S.grill work for windows and ventilators weighing 21kg/sqm using M.S. flats, or M.S. square rods, or combination of M.S. flats and square rods as per approved design, drawing including cutting steel sections and welding the same to required pattern with a coat of red lead primer, cost of materials, fixtures, labour and HOM of machinery complete as per specifications. Ground Floor with all lead and lifts and directions of the Engineer-In-Charge of the work                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    | Kgs  | 234.36            | 95.00                                          | Rupees Ninety Five only                |
| 81    | Providing and fixing M.S.grill work for windows and ventilators weighing 21kg/sqm using M.S. flats, or M.S. square rods, or combination of M.S. flats and square rods as per approved design, drawing including cutting steel sections and welding the same to required pattern with a coat of red lead primer, cost of materials, fixtures, labour and HOM of machinery complete as per specifications. First Floor with all lead and lifts and directions of the Engineer-In-Charge of the work                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | Kgs  | 126.63            | 100.00                                         | Rupees one hundred only                |
| 82    | Providing and fixing in position aluminium windows and ventilators as per approved drawings with sliding shutters using threerack window frame of size 92x31.75mm bottom section 1.3mm thick, weight 1.07kg/m; sides and top sections 1.3 mm, thick, weight 0.933kg/m. shutter frame section comprising top and bottom section of size 40mmx18mm, wall thickness 1.25mm. weight 0.417 kg./m. shutter sideouter 40mmx18mm. wall thickness 1.25mm. weight 0.417 kg/m, shutterinterlock section 40mmx26.7mm wall thickness 1.1 mm. thick, weight 0.469 kg/m, the shutters mounted on nylon rollers with approved qualityof fixtures such as aluminium handles tower bolts etc.; providing andfixing 5.5mm. thick plain glass for shutters fitted with rubber beading allaluminium sections including cutting to required length, joints mitredsubdividing the frame tenonned and rivetted, in the assembled frame, stiffened with end clips for corners, angles etc., and fixed to the walls, lintels, floor beams/cills as the case may be, with necessary steelscrews, raul plugs or teak wood gatties including cutting masonry orconcrete and making good the original surface using cement mortar. (using aluminium | Sqm  | 11.16             | 4500.00                                        | Rupees four Thousand Five Hundred only |

Dr. V. Jay. 5/7

*Gangulu Reddy*

Signature of the Contractor

| SI No | Item Name                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | Unit | Estimate Quantity | Negotiated Rates quoted by Sri GANGULU REDDY A |                                            |
|-------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|-------------------|------------------------------------------------|--------------------------------------------|
|       |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |      |                   | Rate in figures                                | Rate in words                              |
| 70    | Providing 18mm thick cement plaster in single coat with cement mortar 1:4, to brick masonry including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, cost of materials, labour, curing complete as per specifications and direction of the Engineer in charge for Outside Plastering. Ground Floor with all lead and lifts and directions of the Engineer-In-Charge of the work                                                                                   | Sqm  | 217.58            | 250.00                                         | Rspees Two Hundred Fifty only              |
| 71    | Providing 18mm thick cement plaster in single coat with cement mortar 1:4, to brick masonry including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, cost of materials, labour, curing complete as per specifications and direction of the Engineer in charge for Outside Plastering. First Floor with all lead and lifts and directions of the Engineer-In-Charge of the work                                                                                    | Sqm  | 167.57            | 250.00                                         | Rspees Two Hundred fifty only              |
| 72    | Providing Ceramic tiles of approved make shade and size for flooring, treads of steps and landings laid on a bed of 12mm thick, cement mortar 1:3 mix, flush pointing with white cement using colour pigment, including cost of materials, labour, curing, complete as per specifications . size 30 x 30 cms 6mm thick. Ground Floor. with all lead and lifts and directions of the Engineer-In-Charge of the work                                                                                                | Sqm  | 117.62            | 1300.00                                        | Rspees one Thousand Three Hundred only     |
| 73    | Providing Ceramic tiles of approved make shade and size for flooring, treads of steps and landings laid on a bed of 12mm thick, cement mortar 1:3 mix, flush pointing with white cement using colour pigment, including cost of materials, labour, curing, complete as per specifications . size 30 x 30 cms 6mm thick. First Floor with all lead and lifts and directions of the Engineer In-Charge of the work                                                                                                  | Sqm  | 72.80             | 1300.00                                        | Rspees one Thousand Three Hundred only     |
| 74    | Providing Skirting, Dado, rises of steps with colour glazed tiles 6mm thick on 10mm thick cement plaster 1:3 and jointed with white cement slurry over roughj plaster surface (excluding cost of rough plastered surface which should be measured and paid separately) using glazed tiles of approved make and size including cost of materials, labour, Complete as per specifications. size 15 x 15 cms - 6mm thick. Ground Floor. with all lead and lifts and directions of the Engineer-In-Charge of the work | Sqm  | 211.26            | 1650.00                                        | Rspees one thousand Six Hundred Fifty only |

#V. Y → Aug. 5/7

*Gangulu Reddy*

Signature of the Contractor

Page 14 of 21

Executive Engineer (Project)

| SI No | Item Name                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | Unit | Estimate Quantity | Negotiated Rates quoted by Sri GANGULU REDDY A |                                               |
|-------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|-------------------|------------------------------------------------|-----------------------------------------------|
|       |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |      |                   | Rate in figures                                | Rate in words                                 |
| 60    | Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for Stairs (excluding landing) except spiral staircase including cost of all materials, labour complete as per specification. First Floor with all lead and lifts and directions of the Engineer-In-Charge of the work                                                                                                                                                                                                 | Sqm  | 27.80             | 550.00                                         | Rupees Five Hundred Fifty only                |
| 61    | Providing TMT Steel Reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. TMT Bars Fe 500. Ground Floor with all lead and lifts and directions of the Engineer-In-Charge of the work | M.T  | 6.11              | 66000.00                                       | Rupees Sixty Six Thousand only                |
| 62    | Providing TMT Steel Reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. TMT Bars Fe 500. First Floor with all lead and lifts and directions of the Engineer-In-Charge of the work  | M.T. | 3.23              | 66000.00                                       | Rupees Sixty Six Thousand only                |
| 63    | Providing and constructing precast concrete Solid Blocks with compressive strength not less than 3.5 Newton per sqmm with cement mortar 1:4 masonry (quoin, jamb, closer blocks) with Solid Concrete Blocks of size 40x20x20 cms confirming to I.S 2185/1965 in Superstructure including cost of all materials, labour charges, scaffolding, curing complete as per specifications. Ground Floor with all lead and lifts and directions of the Engineer-In-Charge of the work                                           | Sqm  | 250.15            | 1119.00                                        | Rupees one Thousand one Hundred Nineteen only |
| 64    | Providing and constructing precast concrete Solid Blocks with compressive strength not less than 3.5 Newton per sqmm with cement mortar 1:4 masonry (quoin, jamb, closer blocks) with Solid Concrete Blocks of size 40x20x20 cms confirming to I.S 2185/1965 in Superstructure including cost of all materials, labour charges, scaffolding, curing complete as per specifications. First Floor with all lead and lifts and directions of the Engineer-In-Charge of the work                                            | Sqm  | 207.86            | 1100.00                                        | Rupees one Thousand one Hundred only          |

*A. Gangulu Reddy*

Att. V. J. *5/7*

| SI No | Item Name                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | Unit | Estimate Quantity | Negotiated Rates quoted by Sri GANGULU REDDY A |                                       |
|-------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|-------------------|------------------------------------------------|---------------------------------------|
|       |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |      |                   | Rate in figures                                | Rate in words                         |
| 49    | Providing and laying in position reinforced cement concrete of design mix M25 with OPC cement @ 340kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.47 cum with superplasticiser @ 3lts confirming to IS 9103-1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in ground floor level for roof slabs, staircase, lintels, beams, retaining walls, return wall, walls (an thick ness) including attached plasters, columns, pillars, posts, struts, butters, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets including cost of all materials, labour, HOM of machinery, curing, complete as per specifications. Ground Floor with all lead and lifts and directions of the Engineer-In-Charge of the work | Cum  | 20.29             | 7000.00                                        | Rupees Seven Thousand only            |
| 50    | Providing and laying in position reinforced cement concrete of design mix M25 with OPC cement @ 340kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.47 cum with superplasticiser @ 3lts confirming to IS 9103-1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in ground floor level for roof slabs, staircase, lintels, beams, retaining walls, return wall, walls (an thick ness) including attached plasters, columns, pillars, posts, struts, butters, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets including cost of all materials, labour, HOM of machinery, curing, complete as per specifications. First Floor with all lead and lifts and directions of the Engineer-In-Charge of the work  | Cum  | 9.69              | 7000.00                                        | Rupees Seven Thousand only            |
| 51    | Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour complete as per specifications. with all lead and lifts and directions of the Engineer-In-Charge of the work                                                                                                                                                                                                                                                                                                                                                                                                                                                                             | Sqm  | 87.90             | 320.00                                         | Rupees Three Hundred Twenty only      |
| 52    | Providing and laying cement concrete using 20mm and down size granite coarse aggregates and fine aggregates of ready mixed concrete for RCC works laid in 15 cms thick layers and well compacted including vibrating, curing, etc., with all lead and lifts etc complete (exclusive of cost of steel and fabrication charges) Ready Mixed Cement Concrete for Beams, Staircase and Roof with M-25 with all lead and lifts and directions of the Engineer-In-Charge of the work                                                                                                                                                                                                                                                                                                                                                                   | Cum  | 59.42             | 6600.00                                        | Rupees Six Thousand Six Hundred only. |

*A. Gangulu Reddy*

Signature of the Contractor

| Sl No | Item Name                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | Unit | Estimate Quantity | Negotiated Rates quoted by Sri GANGULU REDDY A |                                                 |
|-------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|-------------------|------------------------------------------------|-------------------------------------------------|
|       |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |      |                   | Rate in figures                                | Rate in words                                   |
| 39    | Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts complete as per specifications. Prestressed / Reinforced cement concrete grade M-20 & above with all lead and lifts and directions of the Engineer-In-Charge of the work | Cum  | 5.88              | 1145.00                                        | Rupees one thousand one Hundred Forty Five only |
| 40    | Dismantling cement concrete flooring or plain cement concrete work including removing and conveying the debris to distance upto 200m (within average thickness of 15 cms). with all lead and lifts and directions of the Engineer-In-Charge of the work                                                                                                                                                                                                                                                           | Sqm  | 68.61             | 61.00                                          | Rupees Sixty one only                           |
| 41    | Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts complete as per specifications. Rubble stone masonry in cement mortar with all lead and lifts and directions of the Engineer-In-Charge of the work                       | Cum  | 19.35             | 275.00                                         | Rupees Two Hundred Seventy Five only            |
| 42    | Earthwork in surface excavation in ordinary soil for levelling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe lines and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface levelled and neatly dressed, disposed earth to be levelled after breaking of clods and neatly dressed as per specifications with all lead and lifts and directions of the Engineer-In-Charge of the work | Cum  | 43.64             | 170.00                                         | Rupees one Hundred Seventy only                 |
| 43    | Earth work excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5m in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m after breaking of clods complete as per specification with all lead and lifts and directions of the Engineer-In-Charge of the work                            | Cum  | 130.46            | 300.00                                         | Rupees Three Hundred only                       |
| 44    | Filling available excavated earth (excluding rock) insides of foundations upto plinth in layers not exceeding 20cms. In depth, compacting each deposited layer by ramming after watering with a lead upto 50m. And lift upto 1.5m including cost of all labour complete as per specifications. with all lead and lifts and directions of the Engineer-In-Charge of the work                                                                                                                                       | Cum  | 52.19             | 140.00                                         | Rupees one Hundred Forty only                   |

Signature of the Contractor  
*A. Gangulu Reddy*

| Sl No | Item Name                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              | Unit | Estimate Quantity | Negotiated Rates quoted by Sri GANGULU REDDY A |                         |
|-------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|-------------------|------------------------------------------------|-------------------------|
|       |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |      |                   | Rate in figures                                | Rate in words           |
| 24    | Providing and applying painting in two coats with plastic Emulsion paint of approved brand on wall surface to give an even approved shade after thoroughly brushing the surface, free from mortar drops and other foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour, complete as per specifications and as per the directions of the Engineer in charge with primer with all lead and lifts and directions of the Engineer-In-Charge of the work    | Sqm  | 504.16            | 100.00                                         | Rupees one Hundred only |
| 25    | Providing and applying painting in two coats with plastic Emulsion paint of approved brand on ceiling surface to give an even approved shade after thoroughly brushing the surface, free from mortar drops and other foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour, complete as per specifications and as per the directions of the Engineer in charge with primer with all lead and lifts and directions of the Engineer-In-Charge of the work | Sqm  | 381.46            | 100.00                                         | Rupees one Hundred only |
| 26    | Providing ACE paint to external walls of approved colour and shade over prime's coat after brooming & cleaning the surface and applying two coats of ACE paint with cost of all material, labour, lead lift with loading unloading etc. complete as per direction of Engineer in charge of work. with all lead and lifts and directions of the Engineer-In-Charge of the work                                                                                                                          | Sqm  | 544.76            | 200.00                                         | Rupees Two Hundred only |
| 27    | Applying priming coat over new wood surface and/ or wood based surface after preparing the surface after thoroughly cleaning oil, grease, dirt and foreign matter, sand papering and knotting liquid wood filler, for varnish including cost of materials, labour, complete as per specifications. with all lead and lifts and directions of the Engineer-In-Charge of the work                                                                                                                        | Sqm  | 25.99             | 45.00                                          | Rupees forty five only  |
| 28    | Providing and applying painting two coats (excluding priming coat) on new wood surface and / or wood based surface with enamel paint to give an even shade, cleaning the surface of all dirt, dust and foreign matter, sand papering including cost of materials, labour, complete as per specifications. with all lead and lifts and directions of the Engineer-In-Charge of the work                                                                                                                 | Sqm  | 25.99             | 90.00                                          | Rupees Ninety only      |
| 29    | Providing and applying enamel metal paint two coats (excluding priming coat) over new steel or other metal surface brushing to give an even shade after cleaning oil, grease, dirt and other foreign matter, including cost of materials, labour, complete as per specifications. with all lead and lifts and directions of the Engineer-In-Charge of the work                                                                                                                                         | Sqm  | 113.91            | 90.00                                          | Rupees Ninety only      |

*A Gangulu Reddy*

Signature of the Contractor

*Dr. L. Jay. 573*  
Executive Engineer (Project)

| Sl No | Item Name                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 | Unit | Estimate Quantity | Negotiated Rates quoted by Sri GANGULU REDDY A |                                     |
|-------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|-------------------|------------------------------------------------|-------------------------------------|
|       |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |      |                   | Rate in figures                                | Rate in words                       |
| 15    | Providing 18mm thick cement plaster in single coat with cement mortar 1:4, to brick masonry including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, cost of materials, labour, curing complete as per specifications and direction of the Engineer in charge Providing lime rendering for plastering to wall and ceiling including cost of materials labour curing complete as per specifications Internal wall plastering. with all lead and lifts and directions of the Engineer-In-Charge of the work | Sqm  | 504.16            | 340.00                                         | Rs. Three Hundred Forty only        |
| 16    | Providing 18mm thick cement plaster in single coat with cement mortar 1:4, to brick masonry including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, cost of materials, labour, curing complete as per specifications and direction of the Engineer in charge for Outside Plastering. with all lead and lifts and directions of the Engineer-In-Charge of the work                                                                                                                                        | Sqm  | 544.76            | 300.00                                         | Rs. Three Hundred only              |
| 17    | Fixing of door frames in an existing opening including embedding frame in floor and walls after cutting masonry for holdfasts for embedding holdfast in cement concrete 1:3:6 of 20mm and downsize granite metal painting two coats of coal tar to sides of frame, making good the damages to walls and floor as required and disposal of the debris with lead upto 50 m. including cost of materials, labour, complete as per specifications. with all lead and lifts and directions of the Engineer-In-Charge of the work                               | Sqm  | 5.00              | 1200.00                                        | Rs. one Thousand Two Hundred only   |
| 18    | Providing Honne Wood frames of doors, windows, clerestory windows, ventilators and other frames, wrought, framed or assembled including making plaster grooves ( excluding cost of cement concrete and side clamps ), but including cost of materials, labour, HOM of machineries complete as per specifications. with all lead and lifts and directions of the Engineer-In-Charge of the work                                                                                                                                                            | Cum  | 0.41              | 1,50,000.00                                    | Rs. one lakh Fifty Thousand only    |
| 19    | Providing and fixing in position fully panelled Honne Wood shutters for doors, styles and rails of 40mm thick with bottom and lock rails 180mm wide top rail and styles 100mm wide as per drawing and panels of 25mm thick including cost of materials, labour, HOM of machineries Complete as per Specifications. with all lead and lifts and directions of the Engineer-In-Charge of the work                                                                                                                                                           | Sqm  | 8.55              | 5500.00                                        | Rs. Five Thousand Five Hundred only |

*Gangulu Reddy*

*Dr. Y. J. S. 17*

| SI No | Item Name                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              | Unit | Estimate Quantity | Negotiated Rates quoted by Sri GANGULU REDDY A |                                                      |
|-------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|-------------------|------------------------------------------------|------------------------------------------------------|
|       |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |      |                   | Rate in figures                                | Rate in words                                        |
| 4     | Providing and laying in position reinforced cement concrete of design mix M25 with OPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.7cum and fine aggregates @ 0.47cum, with superplastisizer @ 3lts confirming to IS 9103-1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in ground floor level for roof slabs, staircase, lintels, retaining walls, return walls, walls ( any thickness ) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc., including cost of all materials, labour, HOM of machinery, curing, complete as per specifications with all lead and lifts and directions of the Engineer-In-Charge of the work | Cum  | 17.00             | 7000.00                                        | Rupees Seven Thousand only                           |
| 5     | Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for sides and soffits of beams, beam haunchings, cantilever girders, bressuomers and lintels exceeding 1 m in depth including cost of all materials, labour complete as per specifications. with all lead and lifts and directions of the Engineer-In-Charge of the work                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              | Sqm  | 192.33            | 303.00                                         | Rupees Three Hundred Three only                      |
| 6     | Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for flat surface such as roofs landings balconies and like thickness upto 200 mm including cost of all materials labour complete as per specifications upto 3.50 m from Ground level with all lead and lifts and directions of the Engineer-In-Charge of the work                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | Sqm  | 446.40            | 368.00                                         | Rupees Three Hundred Sixty Eight only                |
| 7     | Providing and laying in Mat for RCC roof at below the steel for avoiding concrete cement slurry as per the requirement of Engineer incharge with all lead and lifts and directions of the Engineer-In-Charge of the work                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | Sqm  | 446.40            | 73.00                                          | Rupees Seventy Three only                            |
| 8     | Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth cills and string courses cost of all materials labour complete as per specifications with all lead and lifts and directions of the Engineer-In-Charge of the work                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | Sqm  | 21.57             | 343.00                                         | Rupees Three Hundred Forty Three only                |
| 9     | Providing and laying cement concrete using 20mm and down size granite coarse aggregates and fine aggregates of ready mixed concrete for RCC works laid in 15 cms thick layers and well compacted including vibrating, curing, etc., with all lead and lifts etc complete (exclusive of cost of steel and fabrication charges) Ready Mixed Cement Concrete for Beams, Staircase and Roof with M-25 with all lead and lifts and directions of the Engineer-In-Charge of the work                                                                                                                                                                                                                                                                                                                                                                                                         | Cum  | 87.71             | 7177.00                                        | Rupees Seven Thousand one Hundred Seventy Seven only |

Signature of the Contractor  
